



# **RATED DRILLING DEPTH:**

3000 m with 5" D.P.

#### SUBSTRUCTURE:

Height: 5.18 m (17 ft) Height under rotary beams: 4.27 m (14 ft) Set Back: 131 mt

#### MAST:

Skytop-Brewster 35 m (115 ft) Capacity: 186 mt

## **CROWN BLOCK:**

No of sheaves: 5+1 Grooved: 1 1/8" Capacity: 222 mt

# **TRAVELLING BLOCK & HOOK:**

Skytop-Brewster HB 245 Capacity: 222 mt

## SWIVEL:

Ideco TL 200 Capacity: 182 mt

## **DRAWWORKS:**

Skytop-Brewster RR 850 900 HP, 2 x Detroit Diesel 12 V-71, 328 kW each

#### **ROTARY TABLE:**

Emsco T 2750, 27 1/2", Capacity: 454 mt



## **POWER PLANT:**

Diesel Engines: 2 x Cat 398, 670 kW each Generators: 2 x AC Uljanik 2 SCS 1002-6, 750 kVA each

#### **MUD SYSTEM:**

Mud Pumps: 2 x Gardner Denver PZ-8 triplex, 580 kW, each pump powered by Cat 3508, 580 kW each Mud Tanks: 5, Total capacity: 190 m<sup>3</sup> Water Tanks: Total capacity: 57 m<sup>3</sup> Shale Shaker: 2 x Swaco Mongoose PT Mud Cleaner: Brandt Dual Tandem Desander: Pioneer T 6 x 6" Desilter: Pioneer T 10 x 4" Mud/Gas Separator: Atmospheric Degasser: Swaco, Vacuum